



RAJIV GANDHI NATIONAL UNIVERSITY OF LAW, PUNJAB

(Established under Punjab Act No. 12 of 2006)

(Accredited with 'A' Grade by NAAC)

SHORT TERM NOTICE INVITING QUOTATIONS

NO. 151/CMW/RGNUL

Dated:-06.02.2025

Rajiv Gandhi National University of Law Punjab Patiala invites sealed quotations from competent and reputed agency/firms/suppliers for following below noted works/ Supply . The quotations is required to be submitted in sealed cover address to The Registrar , **Rajiv Gandhi National University of Law Punjab Patiala** so as to reach the University on or before 4.00 pm on **10.02.2025** duly superscripting the quotation for "Each below noted works/ Supply " on the top of sealed envelope.

S.No.	Brief Description of Work
1	Providing and Fixing of road marking with hot applied Thermoplastic paint at RGNUL new campus, Sidhuwal, Patiala. (As Per Annexure "A")
2	Repair of damaged Gypsum false ceiling in Auditorium & Academic building at RGNUL new campus, Sidhuwal, Patiala. (As Per Annexure "B")
3	Providing and fixing of ACP sheet in front elevation of Auditorium building in RGNUL campus, Sidhuwal, Patiala. (As Per Annexure "C")
4	Supply of Red Door mat roll 12 mtr long 1.2 mtr wide as per Sample.

Terms & Conditions:-

1. The Agency/printer are advise to visit the University in order to examine the sample of above mention **Supply or works** before quoting the rate .
2. The rates should be quoted as shown against the item and should be inclusive of GST/taxes or other charges (FOR) applicable at any point in time.
3. The RGNUL reserves right to accept/reject any or all the Quotations at any time without assigning any reason.
4. Items may be increased or decreased as mentioned above as per the requirement of the university.
5. Any indulging in malpractice or adopting unfair means will be barred from working with the University.
6. Govt. Notified Statutory Dues to be deducted from the bill.
7. Past records of the Agency/firm will be duly considered while awarding the work.


University Engineer.

Cc to:- (i).Notice board

(ii).RGNUL website

Annexure "A"

Providing and Fixing of road marking with hot applied Thermoplastic paint at RGNUL new campus, Sidhuwal, Patiala.

SR.No	CSR NO	DESCRIPTION	Pic	QTY	UNIT	Basic	Pr.	Rate	Amount
1	24.57	Road Marking with Thermoplastic Compound Road marking with hot applied thermoplastic compound 2.5mm thick including reflectorising glass beads @ 0.25kg per sqm area as per IRC:35 1997 complete as per technical clause 803 of MORT&H specifications		152	sqm	616.67	0%	616.67	93733.84
		Total							93733.84

NOTES: - 1. Quoted rates shall be inclusive of all taxes & duties.

2. The above items and any other items if got executed & is available in CSR 2020/DSR 2018 shall also be charged @ ____ % above / less over CSR 2020 + Ceiling premium / DSR 2018. If items are not available either in CSR / DSR shall be paid on market rate for which rate shall be derived by RGNUL & shall be acceptable to the executing agency.

(Signature of the agency with seal)

Annexure "B"

Maintenance & repair of damaged Gypsum false ceiling in Auditorium building at RGNUL new campus, Sidhuwal, Patiala.

SR.No	CSR NO	DESCRIPTION	no.	Length	Width	Height	QTY	UNIT	Basic Rate	premiu m	Rate	Amount
1	8.44	Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable material and stacking of serviceable material within 50 meters lead as directed by Engineer-in-charge	1	11.5	1.5		17.25	Sqm				
							17.25	Sqm	46	5.35%	48.461	836.0
2	13.65	Repair of existing Providing and Fixing ceiling consisting of 12.5mm thick Gypsum Board of any size G.I. Cradling hanged from the ceiling by means of G.I. hanger complete as per drawings, specifications and to the entire satisfaction of engineer-	<u>Same as above</u>				17.25	Sqm				
			2	100	0.1		20.00					
Total							37.25	sqm	1321	0.054	1391.7	51839.8
3	31.36	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S.clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required		37.25	100%		37.25	sqm	206	0.054	217.02	8084.0
4	16.65	Preparation of plastered or concrete surface for painting (including sand papering the surface) using ready mixed cement based wall putty by applying two coats to	SAME AS ABOVE				37.25	sqm	80	0.054	84.28	3139.4
5	16.63	Wall painting with plastic emulsion paint of approved brand and manufacturer to give an even shade (two coats)	SAME AS ABOVE				37.25	sqm	89	0.054	93.762	3492.6
Total												67392
Add 2% contingency												1348
G total												68740

Say ₹ 68,740

NOTES: - 1. Quoted rates shall be inclusive of all taxes & duties.

2. The above items and any other items if got executed & is available in CSR 2020/DSR 2018 shall also be charged @ ____ % above / less over CSR 2020 + Ceiling premium / DSR 2018. If items are not available either in CSR / DSR shall be paid on market rate for which rate shall be derived by RGNUL & shall be acceptable to the executing agency.

(Signature of the agency with seal)

Annexure "C"

Providing and fixing of ACP sheet in front elevation of Auditorium building in RGNUL campus, Sidhuwal, Patiala.

SR.No	DESCRIPTION	QTY	UNIT	Rate	Amount
1	Providing & fixing ACP Sheets of various thickness High Class ISI marked complete in all respect as per the directions of Engineer-in-charge. 4 mm thick ACP Sheet	26.79	Sqm		
	Total				

(Signature of the agency with seal)